Western Belfast Bypass – Aquatic ecology aspects & sharing of lessons learnt



Western Belfast Bypass









- State Highway 1
- Location: Belfast, Christchurch
- Start date: May 2015
- Finish date: Nov 2017
- Client: NZTA
- Client Engineers: Opus
- Contractor: Fulton Hogan
- Aquatic Ecologist: Boffa Miskell
- Contract type: Construction only
- Works: A new 4-lane, 5km long, median divided motorway
- Extends the Christchurch Northern Motorway (SH1) to link with Johns Road (SH1), Christchurch.


Western Belfast Bypass





Western Belfast Bypass





🖬 Fulton Hogan

Seven permanently wetted waterbodies are either in the path or directly adjacent to the WBB alignment:

- at the northern end of the WBB the base of the embankment just skirts the boundary of the Otukaikino Wetland area
- adjacent to the Stoneyhurst Sawmill on Dickeys Rd, the embankment skirts the edge of the Otukaikino Creek
- southwest of the sawmill it crosses Darroch St Drain, Horrell Drain, Whitmore Drain, and Kingsbury Drain
- near where the WBB adjoins Johns Rd the base of the embankment is near one of the lakes at The Groynes.


Throughout the Otukaikino Creek catchment 17 fish species have been recorded on the New Zealand Freshwater Fish Database.





Source: Aquatic assessment of Environmental Effects: WBB, Christchurch, EOS Ecology, Feb 2014





Source: Aquatic assessment of Environmental Effects: WBB, Christchurch, EOS Ecology, Feb 2014





Source: Aquatic assessment of Environmental Effects: WBB, Christchurch, EOS Ecology, Feb 2014

Ecological value of waterbodies




Name	Classifications	Values
Otukaikino Wetland	Regionally Significant Wetland	Significant cultural and terrestrial
Otukaikino Creek	Spring-fed river	High ecological, cultural, and recreational
Darroch Street Drain	Waimakariri Tributary Waterways CCC Utility Waterway CCC Environmental Asset Waterway	Low ecological and cultural
Horrell Drain	Waimakariri Tributary Waterways CCC Environmental Asset Waterway	Moderate ecological and cultural
Whitmore Drain	Waimakariri Tributary Waterways CCC Environmental Asset Waterway	Moderate ecological and cultural
Kingsbury Drain	Waimakariri Tributary Waterways CCC Environmental Asset Waterway	Moderate ecological and cultural
The Groynes (Pond)	CCC Parks and Reserve Feature	Moderate recreational

- Kingsbury, Horrell, and Darroch Street Drains all have abundant eel populations and relatively diverse aquatic invertebrate communities, despite being human-made farm drains.
- Whitmore Drain was not included in the aquatic ecology surveys for this project however, it is expected to have similar ecological value to that of the other farm drains in the area.
- The numerous dry channels also within the WBB project area are likely to have no, or limited, value for aquatic fauna.

Waterbody	Activity	Disturbed footprint
Darroch St Drain (North)	Culvert install / realignment of drain	40m / 20m
Darroch St Drain (South)	Culvert install / re- alignment of drain	20m / 10m
Horrell Drain	Culvert install / realignment of drain	50m / 100m
Horrell Drain (farm access)	Twin culvert / realignment of drain	4m / 10m
Whitmore Drain	Drain filled in	70m
Kingsbury Drain	Drain filled in & new drain to be established	220m / 220m
Sawmill Drain	Culvert install	40m



Western Belfast Bypass—Streams and Drains







Statutory Requirements



Authority	Consent No.	Description
CCC RMA92024944		New designation to allow for the construction and operation of a
	RMA92024944	new section of motorway (4-lane median divided arterial road) as
	CC	an extension to the existing Northern Motorway, referred to as
		the Western Belfast Bypass
ECan CRC144923	Discharge permit to discharge stormwater and other	
EGan	CRC144923	contaminants into land and water
ECan	CRC144924	Land use consent - to use land to disturb excavate and erect
EGan	CKC144924	structures in a watercourse and use land
ECan	CRC144925	Water permit - to dam and divert groundwater and surface water.
50	ECan FPB125120	Flood Protection and Drainage Bylaw – To undertake earthworks
ECan		near Flood protection assets.

Consent Obligations



CRC144923 -

Condition 5: Dewatering water shall be discharged onto or into land and shall not enter surface waterways unless treated.

CRC144923 -

Condition 7b: Discharges from dewatering; shall not, further than 25 metres downstream from the discharge point, result in (iii) visual water clarity greater than 20% as measured upstream and downstream of the discharge.

CRC144925 – Condition 3: Diversion works shall be undertaken in a manner which avoids the stranding of fish in pools or channels.

CRC144924 – Condition 13: The works shall not impede fish passage.

Management Plans

🖬 Fulton Hogan

CEMP


 Highlights aquatic ecology impacts and management approach.

ESDCP

- Highlights waterways of significance and the need to protect the waterways from adverse effects of sediment.
- Highlights key construction related effects on waterways.
- Where temporary diversions are required water will be diverted in such a way as to maintain any existing fish passage.

EWDSDMP

- Mitigation measures to be adopted to address waterway form and revegetation for constructed channels, fish passage, and fish relocation from areas where the waterway will be lost.
- Identification of measures anticipated to be achieved to ensure an ecologically successful realignment of Kingsbury Drain.
- Methods to maintain fish passage during and following completion of the works along the stretches of drain affected by the works.



Waterway Diversion Principles

- The removal of fish shall be undertaken by an aquatic ecologist.
- Aquatic ecologist to be consulted during construction methodology and programming
- Dewatering should be avoided during summer (where practicable).
- Any ponded areas remaining after dewatering shall be checked for stranded fish
- Suitable fish barriers will be installed when working in waterways
- Construction of all new permanent realignment channels will be undertaken "in the dry"
- Incorporate ecologically suitable design, including provisions for fish cover, appropriate in-stream habitat complexity, and planting of ecologically sensitive riparian vegetation.
- Fish passage to be retained
- Velocities are not substantially increased due to the placement of the culvert.



Fish salvage and relocation requirements



As many fish will be removed as possible from the affected waterways prior to dewatering and diversion.

Barriers will be placed within the channels at the upstream (where applicable) and downstream ends of the waterways to prevent fish recolonising the channel once it has been fished out.



Dewatering



Mitigation options:

- Ensure appropriate treatment of the discharge prior to discharge
- Minimise erosion and scour at the discharge point(s)
- Utilise the existing CCC stormwater network
- Ensure an appropriate mixing zone in the water body
- Ensure the discharge does not have a detrimental impact on flora and fauna downstream of the discharge point; and
- Minimise the volume of dewatering water discharged to surface water bodies through reuse and landbased detention and soakage.



Fish Passage (monitoring)



Fish passage to be maintained during construction

Temporary diversions to be inspected by a qualified ecologist at regular intervals

2 hourly monitoring for all dewatering activities whilst works are taking place.



Habitat Monitoring





Constructed channels will need to present habitat of equal or better quality than the channels they have replaced.

Monitoring should occur 6 months after channel commissioning and may continue on an annual basis for four years.

Results to be compared to the preconstruction assessment completed in 2012.

If results indicate a habitat of less value, steps should be taken to improve the value.






















Fish totals



	Longfin	Shortfin	Eel		Giant	Common	Bully	
Site location	eels	eels	species	Inanga	Bully	Bully	species	Total
Darroch St Drain (South)	0	0	0	0	0	0	0	0
Darroch St Drain (North)	1	25	6	0	2	0	0	34
Kingsbury Drain	1	1132	0	2	17	8	0	1160
Whitemore Drain	3	128	0	1	1	2	0	135
Horrell Drain	15	21	955	51	110	212	59	1423
Horrell Drain (Twin								
culverts)	3	61	0	4	0	0	82	150
Sawmill stormwater								
pond	0	89	0	0	0	0	0	89
Sawmill Drain	0	273	0	0	0	0	0	273
Darroch St ditch	0	7	0	0	0	0	0	7
								3271



Images (L to R) Inanga, Giant bully, Upland bully – Source: Freshwater fish fact sheets, Boffa Miskell, August 2017

Site meeting minutes



Aquatic ecologist summary of meeting requirements 24/08/15

Meet on site at old Groynes Drive at 8:30am 24/08/15

Sign in at Safety Station/ Safety Briefing / Ecologists to be escorted onto site

Site contacts;

- Tanya Blakeley 027 437 7183 (Aquatic Ecologist)
- Tim Toomey 027 478 4634 (Darroch St Drain South/Kingsbury Drain)
- Ty Coetzee 027 534 9303 (Site engineer Escort.)
- Ash Mitchell 027 2466 069 (Sawmill Drain / Darroch St Drain)
- Matt Taylor 021 226 2383 (Kingsbury Drain)

Site visits required:

Darroch St Drain - Installation of culvert/diversion works (Southern end)

Date	Activity		
Monday 24 th August	 HBS pre-start Installation of coffer dams (FH Drainage) Pump out of water between coffer dams to land (using fish screen) Sediment to be inspected by Aquastic ecologist for fish rescue Once clearance received from ecologist, works can commence with headwall works. Traps to be released into section of drain to be in filled (by ecologist). 		
	Downstream works can proceed in the dry without ecologist supervision if the head wall is located where there is no flowing water		
Tuesday 25 th August	 H8.5 pre-start Escorted to site Traps to be inspected, and fish released (by ecologist). Traps to be re-instated 		
Wednesday 26 th August	HBS pre-start Escorted to site Traps to be inspected, and fish released (by ecologist). Pump out of water (using fish screens), discharge to land. Sediment to be inspected by Aquatic ecologist for fish rescue		

 Once clearance received from ecologist, works can commence with channel infill.


Kingsbury Drain - Installation of temporary culvert (works scheduled to commence 26/08/15)

Date	Activity
Monday 24 th August	Discuss methodology with ecologist on most efficient way to install B00mm culvert

Sawmill Drain - Fill in ditch/drain with engineered fill (works scheduled to commence 07/09/15)

Date	Activity
Monday 24 th August	 H&S pre-start Discuss methodology with ecologist on most efficient way to fill in the channel.
	AND THE PARTY

Darroch St Drain – Installation of temporary culvert (Northern end) (works scheduled to commence 14/09/15)



Post construction: Habitat monitoring Fulton Hogan

Overall, the post-construction monitoring indicates the ecological health of the constructed channels of Kingsbury and Horrell Drains is at least the same as pre-construction, baseline conditions.

The freshwater fish community found in both Kingsbury and Horrell Drain was more diverse in the constructed channels than found during the baseline survey.

In-fill planting of taller stature species recommended to increase canopy cover and stream shading in the future.



	Baseline (2012) ³	Constructed (2017)
Habitat	Kingsbury Drain	Kingsbury Drain
Width (m)	2.25	2.50
Velocity (m/s)	0	Negligible
Macrophyte depth (m)	0.09	0.26
Substrate composition (%silt/sand:pebbles:small cobbles:large cobbles:boulders)	100-0-0-0-0	0.2.25.52.10
	100:0:0:0:0	0:3:35:52:10
Fine sediment depth (m)	0.06	0.00
Water depth (m)	0.15	0.26
Habitat type (%) (riffle:pool:run)	0:100:100	0:80:20
Aquatic plant cover (% cover of stream bed)	56	46
Aquatic plant description	Watercress, duckweed, <i>Azolla</i>	Watercress, Azolla, water speedwell, duckweed
Riparian vegetation description	Grass and herb mix	Planted flax and Carex, weeds, grasses, bare earth
Macroinvertebrates		
Taxa richness	15	32
MCI ⁴	65.0	74.4
QMCI	2.3	3.1
EPT ⁵ taxon richness (excluding hydroptilids ⁶)	1	3
% EPT (excluding Hydroptilids)	0.6	0.1
Fish		
Species	Shortfin eel, Iongfin eel ⁷	Inanga, longfin eel, shortfin eel

Image: A large longfin eel (At Risk, Declining) captured in Kingsbury Drain during the post construction survey.

Source: WBB Post Construction Monitoring Memo 04-12-18 (T Blakely, K Noakes)

Opportunities for improvement



Opportunities for improvement



Opportunities for improvement



Aquatic Ecology Training

Connecting Nature Connecting People



Accidental discovery of fish

When handling fish you must:

- Call your Environmental Manager
- Use the Emergency Fish Salvage Kit
- Ensure hands are free of sunscreen, oils, and other chemicals
- Wet hands or gloves from the Emergency Fish Salvage Kit with clean stream water prior to picking up fish
- Collect fish in nets, where possible. A child's butterfly net works well
- Be gentle do not squeeze fish, or hold too tightly. Don't pick fish up by gills, tails, or other appendages
- Gently place in a bucket of clean stream water
- Gently release fish into an appropriate stream or waterway nearby, as soon as possible



Aquatic Ecology Training

Connecting Nature Connecting People

🗧 Fulton Hogan

Environmental Taileate E76

Fulton Hogan

Working in water courses – Aquatic Ecology

Working in or near water courses without proper planning and controls can impact on the fish that live in these environments.

Fulton Hogan's Minimum Standard: Our work will not cause harm to any water course without being

in full compliance with the proper authorisation. Always check that we have the appropriate authorisation in place if you ever need to enter any water course or coastal area.

Risks

- Any works involving water courses, including; stream crossings and culvert work,
- bridge works,
- waterway diversions.
- outfall construction or maintenance,
- waterway clearing or maintenance.
- overpumping water in waterways or dewatering.



The fish screen has been overtopped and fish can get in between gaps in the steel plates. This site needs to be reassessed, and possibly fished again.



- Five questions for discussion:
- 1. Will our work require us to work in any water course?
- 2. If so, have we got the proper permission to work in the water course?
- 3. Have we consulted an aquatic ecologist to ensure our works will limit the effect on fish and fish habitat?
- Have we installed the necessary controls to keep fish away from our work site?
 Have we checked pools of water for stranded fish, including nearby waterways if dewatering?

Controls

- Read your consent conditions or permitted activity rules and ensure you understand all conditions
- Obey all requirements and have a formal handover with the consent holder to ensure controls are agreed on. During planning, determine if an aquatic ecologist is
- required for works in water, fish capture and relocation and if required, before works start, engage an aquatic ecologist to remove the fish from the waterway. (Ensure fish screens are installed at either end of the site to stop more fish entering).
- Block the flow to isolate the site, and overpump around the site, or divert flow through a temporary channel in accordance with consent conditions.
- Ensure there is scour protection at the discharge end back into the waterway to limit any erosion.
- If the fish screens or barriers are breached and there is a possibility that fish have re-entered the site, stop work and consult the aquatic ecologist
- If removing mud or other bed material from waterways, check the removed material for any fish buried in the material
- Appropriately sized fish screens must be fitted to all pump intakes in waterways. Check mesh screen size requirements with your Regional Council (usually 3mm). Have a hand net and bucket of water available on site to
- rescue any stranded fish. Regularly inspect the site and controls to make sure
- everything is working and no fish are stranded, including checking nearby waterways for drawdown if dewatering.

An aquatic ecologist should be engaged to capture and relocate fish. Stranded fish should be place

in a bucket of clean water and relocated as soon as practicable to an agreed cation as deter ed by the aquatic ecologist

limit the effect on fish and fish

course?

habitat?

in any water course?

4. Have we installed the necessary controls to keep fish away from our work site?

Five questions for discussion:

2. If so, have we got the proper

permission to work in the water

3. Have we consulted an aquatic

ecologist to ensure our works will

1. Will our work require us to work

5. Have we checked pools of water for stranded fish, including nearby waterways if dewatering?

Aquatic Ecology Training

Connecting Nature Connecting People





Promote awareness

Connecting Nature Connecting People



or Environmen

Minimising environme focus for the project te with ECan to ensure al

Home

the

Around 118,000 plants, shrubs and tr these are grown from seeds and cutti area

News

During the project more than 3,500 r bully and inanga) have been rescued

All M Where the WBB passes over waterw culverts have been designed to allow Grou with native species

My N Exte

New

theHub H

Site cont



More than 3,500 native fish have been reloca

Operation relocation

Thousands of fish are relocated away from work on the Western Belfast project

Nearly 3500 ranges freshauger fish years

captured and rolocated to a suitable tile

of these fish were shortfin exit, but also

risk with declining numbers.

downamen using these methods. The mapping

included longfin web and manga tone of the

native whitebolt species), both of which are at

there were still more in the waterways. So the

Fution Hogen even carefully armored the sop-

law of fine sk and sedmers from the users

bed for Buffa Miskell ecologies to search stanlagh and reactar the fish A function U/00

native fub, mainly shortlin and longfin eets.

rehicaest to soluble downsmam habkar.

Future Hogan WEB Project Manages Bers

new salvaged from the construction area and

Hayward, said the onviormental successes on

the project to date have resulted from all project

The Western Bellant Dypass WIRE project is a N2590M, Skin greenfields section of State Highway I Brough Christinech, which forms part of the New Zealand Roads of National Significance programme. The new motorway will help reduce congestion by bypassing Bullast between the Northern Motorway and SHL at Johns Road.

The Will alignment outsits an historic Roodblain of the Warrskain Rev. decast when would have originally been welands but was chained for familand passues. As pan of the project, but harnan-made pererrial warmanys ware to be calvered, deened, or filled in th allow for building of the new read-

Bofta Makel (anwabdfantala-farind with commissioned by Fulton Hagen to pressee dw prayer's aquaic workey including providing ecological advice on the leconaruction of new waterway channels, maintaining fishpassage troughout the construction works, and Genying our the Tell rollocation as required by the project's ecological management plan. Boffa Mittaul Aquatic Ecologie, D. Tarque Bakalgled the search responsible for the rescue and

relocation of helmease fish from the waterways. This saw Sarya working closely with the Future Hogan mark, to that the fish restaut works were perfectly simed with the cost consourcion sector. The specialised admission of electric ficting was. Degite the enumous surpler of fash captured.


initially used to capture hish and relocate themaway from the construction zone. However, electric fishing is best suled for use in ferrer flowing, surry-bosomed wareways. The waterways within the WEE were slow flowing with a track layer of fine sit and sedment covering the gravel borrors So, a vallery of supporting methods were drem deployed. Fyler mist is hitski, Gee minow state, and Kiwell box sigs were baland with shreed ta food or saw beef, car bracking, and New Jealand's Tannus breatlast group! Marries





soft being actively involved in environmental management.

Trainmental excellence letti jutt a sup down management dive, but rather business as usual for everyone on the project," he used "The awnership of the project by all staff has mean the mole than half of the improvement stees need have come deeply him the field. The earthweeks and change seams ferred an escellent working wiasonship with both Or Tanya Bakely and WEB Environmental Manager, Ontar Seycholl, On mathematic occasions these warns scopped the job and gox. their hands diny helping to whocase fait species. that were found while conducting totaline woks*



- 1. Include ecological requirements in the landscape specification
- 2. Be specific with habitat features
- Do a site walkover with the project ecologist prior to works commencing to ensure a good understanding of programming implications with fishing effort
- 4. Establish some aquatic ecology training sessions for the project team early on in the project
- 5. Have several emergency fish salvage kits on standby
- 6. Work with the ecologist on the best option for fish barrier screens
- 7. Don't just focus on ESC with works near waterways

- 8. Engage some key staff to get involved in the fishing and trapping efforts
- Always include in the fishing programme some resource to 'fishing the sediment'
- 10. Don't underestimate drawdown risks when dewatering near waterways. Ensure a monitoring programme is in place and always have an emergency contingency to direct flow into surface water if levels are dropping
- 11.Ensure habitat monitoring requirements are realistic and undertaken during appropriate seasons
- 12. Acknowledge and reward good effort amongst the crews





Dr Tanya Blakely Senior Ecologist, Principal Christchurch

+64 3 364 4214 <u>Tanya.Blakely@boffamiskell.co.nz</u> <u>http://www.boffamiskell.co.nz</u>



If you would like more information;



Omar Seychell Environmental Manager - Construction

+ 64 27 705 4450

omar.seychell@fultonhogan.com



Thankyou